



Republic of the Philippines
PROVINCE OF ZAMBOANGA DEL NORTE
BIDS AND AWARDS COMMITTEE
Provincial Capitol, Estaka, Dipolog City
Email add: bidsandawards22@gmail.com

November 14, 2023

INVITATION TO BID

The Provincial Government of Zamboanga del Norte through the Bids and Awards Committee (BAC) is inviting interested parties/ bidders to bid for the following contract:

Contract ID:	PR#300(18)23-11-115(M)
Contract Name:	Procurement of Electrical Supplies
Location/Purpose:	Installation of Three-Phase (Ø) Line, for OPAg Monolithic Dome Cold Storage and Packing Facility Project, PAIC, Lower Irasan, Roxas, ZN.
Approved Budget for the Contract (ABC):	P1,314,389.39 (inclusive of all applicable taxes)

- Bidders/ contractors must have an expertise in undertaking a similar project, completed at least two similar contracts which the equivalent amount is at least 25% of the proposed project for bidding within the last three years.
- Bidders are inform that the delivery term is 30 calendar days upon receipt of Notice to Proceed.
- Bidders/ Contractors shall submit their one (1) copy sealed envelope containing their technical and financial documents
- Documents submitted must be in accordance with the checklist provided and must have a corresponding label or name plates.
- The eligibility check/ screening as well as the Preliminary Examination of Bids shall use the non- discretionary "pass/ fail" criteria.
- Post qualification of the Lowest/ Single bids shall be conducted.
- All particulars relative to Eligibility Statement and Screening, Bid Security, Performance Security, Evaluation of Bids, Post Qualification and Award of the Contract shall be governed by the pertinent provision of RA 9184 and its Implementing Rules and Regulations (IRR).
- All bids must be accompanied by a bid security in any of the acceptable forms in the amount stated in ITB Clause 14.
- Bidding is restricted to Filipino Citizens/ sole proprietorships, partnerships or organizations with at least sixty percent (60%) interest or outstanding capital stock belonging to citizens of the Philippines, and to citizens or organizations of a country the laws or regulations of which grant similar rights or privileges to Filipino citizens, pursuant to RA No. 5183.

The schedules of activities are listed as follows:

BAC ACTIVITIES	SCHEDULE
Advertisement / Posting	November 15 - 21, 2023
Pre-bid Conference	November 23, 2023 @ 09:00AM
Availability and Issuance of Bidding Documents	November 15, 2023 – December 07, 2023 @ 08:30AM
Deadline for the Submission of Bids	December 07, 2023 @ 08:30 AM
Bid Opening and Evaluation	December 07, 2023 @ 09:00AM

- Payment for bidding documents is a non- refundable amount of **Five Thousand Pesos Only (Php5,000.00)** payable to the Office of the Provincial Treasurer, Provincial Capitol Building, Dipolog City.
- Prospective Bidders may obtain further information from the Office of the Bids and Awards Committee, Provincial Capitol Building during office hours @ 8:00AM - 5:00PM.
- Bids must be duly received by the BAC Secretariat through manual submission at the address stated above.
- The Provincial Government of Zamboanga del Norte reserves the right to reject any and all bids, declare a failure of bidding, or not award the contract at any time prior to contract award in accordance with Sections 35.6 and 41 of the 2016 revised IRR of RA No. 9184, without thereby incurring any liability to the affected bidder or bidders.
- **Bidding Documents will be electronically uploaded to the Philgeps website of the Provincial Office of Zamboanga del Norte at bidsandawards22@gmail.com.**

ATTY. RAFAEL R. OSABEL, JR.
BAC Chairman

Annex A:

Procurement of Electrical Supplies

PR# 300(18)23-11-115(M)

ABC: **PL,314,389.39**

I. POLE TOP ASSEMBLY UNIT

1. 4 sets C7
2. 2 sets C14 (A14 Construction)

II. TRANSFORMER ASSEMBLY UNITS

3. 1 set G310

III. GROUNDING ASSEMBLY UNITS

4. 4 sets M2-11A

IV. GUY ASSEMBLY UNITS

5. 1 set E1-2
6. 2 sets E6-2

V. ANCHOR ASSEMBLY UNITS

7. 5 sets F1-3

VI. POLE

8. 2 pcs 35 Feet
9. 1 pc 40 Feet

VII. CONDUCTOR ASSEMBLY

Bare

10. 1.173 kms #1/0, AWG, ASCR

VIII. MISCELLANEOUS ASSEMBLY UNITS

11. 6 sets M5-10
12. 1 set M5-27 (Truss Guy)
13. 5 pcs Anchor, Expanding, 10,000 Pounds, 8 way, Galvanized Steel
14. 5 pcs Bolt, Thimble Eye, 5/8" x 10", Angle Type, HDG Forged
15. 16 pcs Bolt, Carriage 3/8" x 4-1/2"
16. 12 pcs Bolt, Double Arming, 5/8" x 22"
17. 4 pcs Bolt, Oval Eye 5/8" x 12"
18. 2 pcs Bolt, Machine, 1/2" x 6"
19. 6 pcs Bolt, Machine, 1/2" x 10"
20. 1 pcs Bolt, Machine, 5/8" x 8"
21. 6 pcs Bolt, Machine, 5/8" x 10"
22. 2 pcs Bolt, Machine, 5/8" x 12"
23. 6 set Brace, Angular, 60", Steel HDG (45x45x5mm)
24. 2 pcs Brace, Sidearm, Diagonal, 7 feet
25. 2 pcs Bracket, Clevis Deadend without Spool
26. 1 pc Clamp, Anchor Rod Bonding, Single Eye
27. 8 pcs Clamp, Loop Deadend, #1/0 ACSR
28. 12 pcs Clamp, Deadend Strain, #1/0 ACSR
29. 6 pcs Clamp, Pole Mounting Adapter (6-7), Type RL
30. 10 pcs Guy Deadend Grip, 3/8"
31. 4 pcs Clamp, Guy Bond
32. 4 pcs Clevis, Secondary Swinging without Spool
33. 1173 mtrs Conductor, Bare, ACSR #1/0, AWG 6/1
34. 14 pcs Connector, Compression, YHO 150, #3-1/0 ACSR Run to #16-#2
35. 12 pcs Connector, Compression, YHO 300, #1/0-#2/0 ACSR Run to #1/0-#2/0
36. 4 pcs Connector, Ground Rod (clamp) for 5/8" Steel Rod
37. 6 pcs Pin, Crossarm, Long Shank, 1" Thread Ø, 20" Long, HDG Forged
38. 6 set Cutout and Arrester Combination, Polymer
39. 6 pcs Insulator, Pin Type, Porcelain, ANSI, Class 55-5
40. 6 pcs Insulator, Spool, 3" ANSI, Class 53-4
41. 12 pcs Insulator, Suspension, Polymer, 15kv
42. 12 pcs Nut, Eye, 5/8", Conventional
43. 16 pcs Nut, Lock, Mf Type, 3/8"
44. 8 pcs Nut, Lock, Mf Type, 1/2"
45. 57 pcs Nut, Lock, Mf Type, 5/8"
46. 5 pcs Rod, Anchor, Threaded, Double Eye, 3/4" x 8"

47. 8 set Rod, Armor, Performed, #1/0 ACSR, Single Support
 48. 4 pcs Rod, Ground Steel, Galvanized, 5/8" x 10'
 49. 1 set Truss Guy for Down Guy, 36"
 50. 55 pcs Washer, Square, Flat, 2-1/4"x2-1/2"x13/16" Ø Hole
 51. 8 pcs Washer, Round, 1-3/8" Ø with 9/16" Ø Hole
 52. 64 ft Wire, Tire, Aluminum Alloy, Soft, #4 AWG
 53. 8 ft Wire, Tape, Armor, Aluminum Alloy, 0.5" x 0.3"
 54. 173 ft Wire, Grounding, Aluminum Alloy, 3 Strand, #4 AWG
 55. 3 units 80 KVA Distribution Transformer
 56. 250 ft Wire Guy, Steel, 3/8" 7 Strand
 57. 2 pcs Pole, Steel, 35' (3.0mm)
 58. 1 pcs Pole, Steel, 40' (3.0mm)
 59. 10 pcs Crossarm, Steel, 3"x4"x8", 3.0mm
- ***Nothing Follows***