



September 06, 2024

INVITATION TO BID

The Provincial Government of Zamboanga del Norte through the Bids and Awards Committee (BAC) is inviting interested parties/ bidders to bid for the following contract:

Contract ID:	PR#300/200-24-09-349(O)
Contract Name:	Construction of 1 -Unit - 2 Classroom Sto. Tomas Elementary School Building Sto. Tomas, Municipality of Mutia, Zamboanga del Norte
Location/Purpose:	For the use in the Construction of 1 -Unit - 2 Classroom Sto. Tomas Elementary School Building Sto. Tomas, Municipality of Mutia, Zamboanga del Norte.
Approved Budget for the Contract (ABC):	P2,242,188.22 (inclusive of all applicable taxes)

- Bidders/ contractors must have an expertise in undertaking a similar project, completed at least two similar contracts which the equivalent amount is at least 50% of the proposed project for bidding within the last three years.
- Bidders are inform that the delivery term is 138 calendar days upon receipt of Notice to Proceed.
- Bidders/ Contractors shall submit their one (1) copy sealed envelope containing their technical and financial documents
- Documents submitted must be in accordance with the checklist provided and must have a corresponding label or name plates.
- The eligibility check/ screening as well as the Preliminary Examination of Bids shall use the non- discretionary "pass/ fail" criteria.
- Post qualification of the Lowest/ Single bids shall be conducted.
- All particulars relative to Eligibility Statement and Screening, Bid Security, Performance Security, Evaluation of Bids, Post Qualification and Award of the Contract shall be governed by the pertinent provision of RA 9184 and its Implementing Rules and Regulations (IRR).
- All bids must be accompanied by a bid security in any of the acceptable forms in the amount stated in ITB Clause 14.
- Bidding is restricted to Filipino Citizens/ sole proprietorships, partnerships or organizations with at least sixty percent (60%) interest or outstanding capital stock belonging to citizens of the Philippines, and to citizens or organizations of a country the laws or regulations of which grant similar rights or privileges to Filipino citizens, pursuant to RA No. 5183.

The schedules of activities are listed as follows:

BAC ACTIVITIES	SCHEDULE
Advertisement / Posting	September 07 - 13, 2024
Pre-bid Conference	September 17, 2024 @ 09:00 AM
Availability and Issuance of Bidding Documents	September 07 - 30, 2024 @ 08:30AM
Deadline for the Submission of Bids	September 30, 2024 @ 08:30 AM
Bid Opening and Evaluation	September 30, 2024 @ 09:00AM

- Payment for bidding documents is a non- refundable amount of **Five Thousand Pesos Only (Php5,000.00)** payable to the Office of the Provincial Treasurer, Provincial Capitol Building, Dipolog City.
- Prospective Bidders may obtain further information from the Office of the Bids and Awards Committee, Provincial Capitol Building during office hours @ 8:00AM - 5:00PM.
- Bids must be duly received by the BAC Secretariat through manual submission at the address stated above.
- The Provincial Government of Zamboanga del Norte reserves the right to reject any and all bids, declare a failure of bidding, or not award the contract at any time prior to contract award in accordance with Sections 35.6 and 41 of the 2016 revised IRR of RA No. 9184, without thereby incurring any liability to the affected bidder or bidders.
- **Bidding Documents will be electronically uploaded to the Philgeps website of the Provincial Office of Zamboanga del Norte at bidsandawards22@gmail.com.**

Atty. RAFAEL R. OSABEL, JR.
 BAC Chairman

Annex:

Construction of 1 -Unit - 2 Classroom Sto. Tomas Elementary School Building Sto. Tomas, Municipality of Mutia, Zamboanga del Norte

PR# 300/200-24-09-349(O)

ABC: P2,242,188.22

ITEM	ACTIVITY DESCRIPTION	UNIT	QTY
PART A	GENERAL REQUIREMENTS		
B.3	Permits and Clearances	l.s	1.00
B.5	Project Billboard / Signboard	ea	1.00
B.7(2)	Occupational Safety and Health Program	l.s	1.00
B.9	Mobilization/Demobilization	l.s	1.00
PART B	OTHER GREQUIREMENTS		
A.1.1(3)	Provision of Field Office for the Engineers	month	4.59
A.1.4(1)	Provision of Progress Photographs	ea	140.00
PART C	CIVIL WORKS		
803(1)a	Structure Excavation (Common Soil)	m ³	48.98
804(4)	Gravel Bedding	m ³	16.73
902(1)	Reinforcing Steel of Reinf. Concrete for One-Storey, Grade 40	kgs	2,085.84
903(2)	Formworks and Falseworks (for one -storey building)	m ²	120.93
900(1)c2	Structural Concrete for Footing & Slab on Fill (Class A, 28 days)	m ³	16.91
900(1)	Structural Concrete for Column, Beam (Class A, 28 days)	m ³	7.04
PART D	PLUMBING WORKS		
1002(4)a	13mmØ-50mmØ Polyvinyl Chloride Pipe (PVC), Blue Pipe	pc	10.00
1001(1)a	50mmØ-100mmØ PVC Pipe, Series 1000	m	35.91
1002(5)	Water Closet/ Urinal with Complete Accessories	set	2.00
1002(5)	Wall Hung/ Countertop/ Under Counter Lavatory with Complete Accessories	set	2.00
1002(5)	Faucet	pc	4.00
PART E	STEEL WORKS		
1047(2)c	Structural Steel Purlins	kgs	1,211.58
1047(3)b	Metal Structure (Sagrods)	pc	100.00
1047(3)c	Metal Structure (Turnbuckle)	pc	16.00
1047(3)d	Metal Structure (Crossbracing)	pc	16.00
1014	Prepainted Metal Sheets (Rib Type, Long Span, above 0.427mm thk.)	m ²	191.40
1013(2)a	Fabricated Metal Roofing (Ridge Roll)	m	19.35
1013(2)b	Fabricated Metal Roofing (Flashing)	m	58.25
1002(2)a	13mmØ-50mmØ Galvanized Iron Pipe	pc	4.00
PART F	ARCHITECTURAL WORKS		
1046	100mm thk CHB Non Load Bearing	m ²	231.96
1027(1)	Cement Plaster Finish	m ²	342.96
1003(1)	6.00 mm Ordinary Plywood Framing Ceiling (Interior)	m ²	130.50
1003(1)	4.5mm Fiber Cement Board Framing Ceiling (Exterior)	m ²	66.50
1003(2)	6.00 mm Fiber Cement Board Metal Frame Double Wall Partition	m ²	21.00
1018	Unglazed Tiles	m ²	4.50
1018(1)	Glazed Tiles	m ²	9.60
1002(5)h	Floor Drain Plates	set	2.00
1010(1)	Frames (Jambs)	set	4.00
1010(2)b	Wooden Panel Door	m ²	7.56
1043(1)	PVC Doors and Frames (set)	m ²	2.52
1009(1)a	Jalousie Window (Glass)	m ²	18.96
1032(1)c	Prepainted Metal Sheets(Rib Type, Long Span, below 0.427mm thk	m ²	42.60
1032(1)b	Painting Works (Wood Painting)	m ²	57.12
1032(1)a	Painting Works (Masonry Painting)	m ²	206.44
1004(2)	Finishing Hardware	set	4.00

PART G	ELECTRICAL WORKS		
1100	Junction/Utility/Square Box	<i>pc</i>	36.00
1100(30)	Conduit Works, Boxes and Fittings	<i>l.s</i>	1.00
1101(2)	1.6mm ² – 5.5mm ² Electric Wire (TW/THHN/TWHN ²)	<i>m</i>	400.00
1101(2)	8.00mm ² – 22mm ² Electric Wire (TW/THHN/TWHN ²)	<i>m</i>	40.00
1101	Switches	<i>set</i>	6.00
1101	Duplex Convenience Outlet	<i>set</i>	10.00
1103(1)	Lighting Fixtures	<i>l.s</i>	1.00
1102	Panel Board with Main Breaker / Branches, 3 Wires, 1 Neutral, 50 Amp. – 200 Amp.	<i>set</i>	1.00
1106(9)	LCD, LED Monitor	<i>set</i>	2.00
1200(4)b	Propeller Fan	<i>set</i>	4.00
	Nothing Follows		